

15-101-20042-00-00

Form CP-3
Rev. 6-4-68

KANSAS

18

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1972
11-01-1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John Eaton,

Complete Address Shields, Kansas. 67874

Lease Name Shramek Well No. 1

Location CSE-SE Sec. 36 Twp. 18 Rge. (E) (W) 27

County Lane Total Depth 4600'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Hellar Drilling Company, Incorporated,

Address 339 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 8:00 AM Day 3 Month 11 Year 1972

The above well was plugged as follows:

253'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 525'.

Circulated hole with heavy mud. Pulled DP to 750' and displaced 110 Cu. Ft. cement
thru DP from 750' to 425'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 3 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. D. Fisher
Well Plugging Supervisor

INVOICED

DATE 11/8/72
INVOICE NO. 6581-U