

15-101-20013-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 2 1972  
10-02-1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Mull Drilling Company, Incorporated.

Complete Address P. O. Box #328, Attica, Kansas.

Lease Name McPadden Well No. 1

Location CNW-SW Sec. 15 Twp. 18 Rge. (E) (W) 27

County Lane Total Depth 4630

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Incorporated,

Address Box #698, Great Bend, Kansas. License No. 670

Operation Completed: Hour 1:00 PH Day 27 Month 9 Year 1972

The above well was plugged as follows:

215'--8 5/8" Surface casing, cement circulated with 155 Sx.  
493'--4 3/4" Production casing cemented on bottom with 100 Sx. Top of cement @ 3974'  
(Temperature Survey). Top perforations from 4288' to 4298'. Well plugged back to  
4330'.

Pushed plug to 4200', sanded well back from 4200' to 4175' and set 4 Sx. cement with  
dump bailer. Pulled 4 3/4" casing (2500') and squeezed well initially with 5 sacks hulls  
and 12 sacks gel and followed with 110 Cu. Ft. cement from 900' to 575' then 9 sacks  
gel from 575' to 225' and followed with 30 Cu. Ft. cement from 225' to 150' then 3  
sacks gel from 150' to 30' and finally 10 Cu. Ft. cement from 30' to bottom of cellar.  
Maximum pump-in pressure-500#. Final shut-in pressure-300#. (Work by Globe Cementing).  
I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Pichler*  
Well Plugging Supervisor

INVOICED

DATE 10-2-72

INV. NO. 6399-02