



15-101-2003-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1972
CONSERVATION DIVISION
Wichita, Kansas
10-02-1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Incorporated,

Complete Address: P. O. Box #328, Attica, Kansas.

Lease Name: McFadden Well No. 1

Location: CNW-SW Sec. 15 Twp. 18 Rge. (E)(W) 27

County: Lane Total Depth 4630' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

215'--8 5/8" Surface casing, cement circulated with 155 Sx.

4493'--4 3/4" Production casing cemented on bottom with 100 Sx. Top of cement @ 3974' (Temp. Survey). Well plugged back to 4330'. Top of perforations 4288' to 4298'.

Push plug to 4200', sand back to 4175' and set 4 Sx. cement with dump bailer. Pull 4 3/4" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. S. Nichols
Conservation Division Agent