



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 SEP 22 1964
 09-22-1964
 CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Marion Helberg of Empire Drilling Co., has this date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Time Petroleum Company,

Complete Address: 815 Union National Building, Wichita, Kansas.

Lease Name: Doerschlag Well No. 1

Location: CSE-SE Sec. 4 Twp. 18 Rge. (E) (W) 27

County Lane Total Depth 4680 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Helberg was instructed to plug the well as follows:

97'--8 5/8" Surface pipe, cement circulated with 60 Sx.

Circulate hole with heavy mud, set plug @ 700' and 20 Sx. cement.

" " 120' with 1/2 sk hulls & 20 Sx. cement.

" " 40' with 1/2 sk hulls & 10 Sx. cement.

Very truly yours,

M. D. Nichols
 Conservation Division Agent