



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION MAR 13 1974 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Incorporated,

Complete Address: P. O. Box #18407, Wichita, Kansas.

Lease Name: Koehler Well No. 2

Location: N/2-NE-NW Sec. 19 Twp. 17 Rge. (E)(W) 27

County: Lane Total Depth 4610' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

361'--8 5/8" Surface casing, cement circulated with 250 Sx. Top of Dakota section @ 700'.

Circulate hole with heavy mud. Pull DP to 925' and displace 110 Cu. Ft. cement thru DP. Pull DP to 375' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1 sack hells and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

[Signature] Conservation Division Agent