

State of Kansas



15-101-20130-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 P. O. Box 17027 3830 S. Meridian
 WICHITA, KANSAS 67217

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 15 1974
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Wilmer Dreiling of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Dreiling guarantees payment of the plugging fee.

Operator's full Name: Mallonee-Mahoney, Incorporated,

Complete Address: 925 Sutton Place, Wichita, Kansas.

Lease Name: L. Waterson Well No. 1

Location: NE-1/4-11W Sec. 18 Twp. 17 Rge. (E)(W) 27

County: Lane Total Depth 4645' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dreiling was instructed to plug the well as follows:

342'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 775'.

Circulate hole with heavy mud. Pull DP to 1000' and displace 110 Cu. Ft. cement thru DP. Pull DP to 340' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

K. L. Nichols
 Conservation Division Agent