

State of Kansas



15-101-2002-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAP Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 9 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dolbort Adams of Forbes Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Adams guarantees payment of the plugging fee.

Operator's full Name: Ronald Russ Prater,

Complete Address: 501 Fourth National Bank Bldg., Wichita, Kansas.

Lease Name: Brown Well No. 1

Location: NF-SF-SW Sec. 36 Twp. 17 Rge. (E)(W) 27

County: Lane Total Depth 1570 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Adams was instructed to plug the well as follows:

340'--8 5/8" Surface casing, cement circulated with 322 Sx.
4551'--14" Production casing cemented on bottom with 125 Sx. Open hole
completion.

Sand well back to 4540' and set 3 Sx. cement with dump bailor. Pull 5 1/2"
casing and squeeze well with 5 sacks hulls, 30 sacks gel and 130 Sx.
cement, staged.

Very truly yours,

M. L. Nichols

Conservation Division Agent