

To: 1  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION App.  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 101-21,022 -00-00  
SE SE NW, SEC. 34, T 17 S, R 27 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 3680

2970 feet from S section line

3020 feet from E section line

Lease Name Whipple Well # 34-6

County Lane Lane 151.45

Operator: L.B. Industries, Inc.

Name & Address 12200 E. Briarwood Ave., Ste. 250

Well Total Depth 4660 feet

Conductor Pipe: Size 8 5/8 feet 302

Surface Casing: Size        feet       

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated       

Plugging Contractor Halliburton License Number       

Address P.O. Box 428, Hays, KS 67601

Company to plug at: Hour: 11 a.m. Day: 9 Month: 9 Year: 19 95

Plugging proposal received from Allen Worth

(company name) Halliburton (phone) 913-625-3431

were: 4 1/2" at 4626' w/200 sx cement, PBD 4540', Perfs at 4206-16', DVD at 2040' w/475 sx cement, circulated to 0'

1st plug pump 275 sx cement with 300 lbs. hulls mixed in

with first 25 sx cement.

Check annulus.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:30 p.m. Day: 9 Month: 9 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped 275 sx cement with 300 lbs. hulls mixed with first

25 sx cement.

Annulus pressured up to 500#.

Remarks: Used 60/40 Pozmix 8% gel by HOWCO. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

1 N.W. 1/4  
(and do not) observe this plugging.

DATE 9-25-95

INV. NO. 43589

Signed Steve Durrant  
(TECHNICIAN)