

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-20,880-00-00

NW/4, Sec. 33, T 17 S, R 27 W

990 feet from N/W section line

1320 feet from W/W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name NEELEY "B" Well # 1

Operator: A.L. ABERCROMBIE, INC  
Name &  
Address 801 UNION CENTER  
WICHITA, KS 67202

County LANE

Well Total Depth 4600 feet 149.50

Conductor Pipe: Size \_\_\_\_\_ feet \_\_\_\_\_

Surface Casing: Size 8 5/8 feet 402

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 8 AM Day: 26 Month: Nov Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Wayne Shively

(company name) Abercrombie (phone) \_\_\_\_\_

were: to use 60/40 Pozmix, 2% gel-3% CC and spot  
1<sup>ST</sup> plug @ 2100' w/60 s/l - 2<sup>ND</sup> plug @ 1500' w/50 s/l  
3<sup>RD</sup> plug @ 450' w/40 s/l - 4<sup>TH</sup> plug @ 40' w/solid  
bridge, plug and 10 s/l to surface. Circulate  
15 s/l in the cathole.

Signed R. Barluttan  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11 AM Day: 26 Month: Nov Year: 19 83

ACTUAL PLUGGING REPORT plugged as ordered,  
Cementing by Sun Cementing.  
Cement ticket # 16788

Remarks: \_\_\_\_\_

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS  
DEC 1 - 1983

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

12-8-83  
7075-W

Signed R. Barluttan  
(TECHNICIAN)