

To: 1 070949
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,491 -00-01
150' W of
NW SE NW, SEC. 32, T 17 S, R 27 W/E
3630 feet from S section line
3780 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144
Operator: Mull Drilling Company, Inc.
Name & Address: P.O. Box 2758
Wichita, KS 67201

Lease Name Spruill Well # 1
County Lane 157.12
Well Total Depth 4650 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 404

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 31 Month: 5 Year: 19 91

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4652' w/125 sx cement, PBSD 4400', Perfs at 4196-4200'

1st plug sand back to 4145' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 5 sx gel and 50 sx cement at 2000',

3rd plug pump .80 sx cement at 1250',

4th plug pump 50 sx cement at 430'. 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 31 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4145' and dumped 5 sx cement on top of sand through bailer,

2nd plug shot casing at 1250' and pumped 80 sx cement,

3rd plug shot casing at 800' and pulled to 430' and pumped 50 sx cement,

4th plug pulled casing and topped off with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 7 1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 800' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.) observe this plugging.

Signed Dan Jordan
(TECHNICIAN)

DATE 6-17-91
INV. NO. 32164