

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101- 20,915 -00-00
NE/4 , Sec. 32 , T 17 S, R 27 W/E
2310 feet from N/~~S~~ section line
1650 feet from ~~XX~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Spruill Well # B-1

Operator: A. L. Abercrombie, Inc.
Name & 801 Union Center
Address Wichita, KS 67202

County Lane

Well Total Depth 4650 feet 151.12

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 404

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 7:00 pm Day: 4 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Wayne Shively

(company name) Abercrombie Drilling (phone) 913-743-6308

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 2100' with 50 sx cement

2nd plug at 1000' with 40 sx cement

3rd plug at 450' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement.

Signed J. A. Mey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:30 am Day: 5 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement, 2nd plug at 1000' with

40 sx cement, 3rd plug at 450' with 50 sx cement, 4th & 5th plugs - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate

rathole with 15 sx cement.

Remarks: Use 60/40 Pozmix with 2% gel, 3%cc. by Sun Cementing.

I hereby certify that the above plugging instructions were given as herein stated
and that I (~~XXX~~ / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
2-13-84
FEB 08 1984
CONSERVATION DIVISION
Wichita, Kansas
0163
2-5

Signed J. A. Mey
(TECHNICIAN)