

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,898-00-00
SWNWSE, SEC. 31, T 17 S, R 27 W/4
1650 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198
Operator: A. Scott Ritchie
Name & Address 125 N. Market
Ste 950
Wichita KS. 67202

Lease Name J. Erskin Well # 1
County Lane 159.78
Well Total Depth 4565 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 370'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pullers License Number 6050
Address Box 347, Chase Kansas 67524

Company to plug at: Hour: 11:00am Day: 8 Month: November Year: 1985

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pullers (phone) 316-938-2457

work: To pump down 4 1/2" casing with 2 sx hulls -
30sx of cement - 10sx gel - 4 1/2 wiper plug - 140sx cement
4 1/2 casing set @ 4565' 4 1/2" casing DV @ 2042
with .550 sx of cement.
4 1/2 casing perforated @ 4519.5 to 4524

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30pm Day: 8 Month: November Year: 1985

ACTUAL PLUGGING REPORT Pumped down 4 1/2" casing with 2sx hulls
30 sx of cement - 10sx gel - 4 1/2" wiper plug - 140sx
of cement Maximum pump pressure 1900 psi
Shut in pressure 1000psi

Remarks: Allied Cementing pumped 60/40 pozmix 6% gel cement
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE NOV 22 1985
INV. NO. 11153

STATE CORPORATION COMMISSION
SIGNED Richard W. Lacey
(TECHNICIAN)
NOV 14 1985