

1 070713

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,506 -00-00

SE NE SE, SEC. 31, T 17 S, R 27 W/E

1650 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Spruill Well # 1

Operator: Ritchie Exploration, Inc.

County Lane 150.67

Name & Address 125 North Market, Suite 1000

Well Total Depth 4636 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 364

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Ritchie Exploration, Inc. License Number 4767

Address 125 North Market, Suite 1000, Wichita, KS 67202

Company to plug at: Hour: 9:30 a.m. Day: 10 Month: 8 Year: 19 89

Plugging proposal received from Bennie Dills

(company name) Ritchie Exploration, Inc. (phone) 316-793-8969

were: 4 1/2" at 4628' PRTD 4570' Perfs at 4403-4579' (3 sets) Squeezed at 1545-60' W/250 sx

1st plug pump 2 sx hulls and fill up 4 1/2" (approx. 150 sx cement),

2nd plug pump 100 sx cement down annulus.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 a.m. Day: 10 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 500 lbs. hulls and 90 sx ATL cement down 4 1/2",

Maximum pressure 1000 psi and shut in 800 psi.

2nd plug pumped 100 sx ATL cement down annulus, Maximum pressure 800 psi and shut in 100 psi.

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1989

Remarks: Used ATL cement by Allied. No casing recovery. CONSERVATION DIVISION
(if additional description is necessary, use BACK of this form.) Wichita, Kansas

observe this plugging.

INVOICED

DATE 8-18-89

Signed Dan Godwin
(TECHNICIAN)

INV. NO. 25679

8-10