

1020144

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,943-00-00 <sup>R</sup>  
NW, SEC. 31, T 17 S, R 27 <sup>WEX</sup>

2310 feet from ~~NW~~ section line  
990 feet from ~~WEX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6879

Lease Name Bernitta Wheatcroft B-1

Operator: Solar Petroleum, Inc.  
Name & Address 1099 - 18th St., Suite 2900  
Denver, CO 80202-1999

County            Lane             
Well Total Depth 4705 152.92 feet  
Conductor Pipe: Size            feet  
Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well            Gas Well            Input Well            SWD Well            D&A X

Other well as hereinafter indicated           

Plugging Contractor H-30, Inc. License Number 5107

Address 251 North Water, Wichita, KS 67202

Company to plug at: Hour: 6:30 pm Day: 11 Month: March Year: 19 84

Plugging proposal received from Ed Jantz

(company name) H-30, Inc. (phone) 316-792-7691

were: to fill hole with heavy mud and spot cement through drill pipe.

- 1st plug at 2075' with 50 sx cement
- 2nd plug at 1290' with 60 sx cement
- 3rd plug at 410' with 50 sx cement  
solid bridge
- 4th plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 6th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by [Signature]  
(TECHNICIAN)

Plugging Operations attended by Agent?: All            Part            None X

Operations Completed: Hour: 8:45 pm Day: 11 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2075' with 50 sx cement, 2nd plug at 1290' with 60 sx cement, 3rd plug at 410' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 19 1984

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied  
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

I (did / did not) observe this plugging.

3-22-84  
089a  
3-11

Signed [Signature]  
(TECHNICIAN)