

DEC 26 1986

API NUMBER 15- 101-21,352 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NW SE, SEC. 14, T 17 S, R 27 W/E
2310 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Hagans Well # 1-14
County Lane 148.88

Operator: Landmark Oil Exploration, Inc.
Name & Address: 110 S. Main, Suite 510
Wichita, KS 67202

Well Total Depth 4581 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 12 p.m. Day: 26 Month: 12 Year: 19 86

Plugging proposal received from Wally Towns

(company name) Abercrombie Drilling, Inc. (phone) 913-462-2123

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2635' GL
Anhydrite 2040-71'

1st plug at base Anhydrite with 50 sx cement, 2nd plug at base Cheyenne with 80 sx cement,

3rd plug at 50' below surface casing with 50 sx cement,

4th plug at 40' to surface with 10 sx cement, 5th plug to circulate rathole with 10 sx

cement, 6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2:15 p.m. Day: 26 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2050' with 50 sx cement,

2nd plug at 1250' with 70 sx cement,

3rd plug at 300' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INFORMED (operator did not) observe this plugging.

DATE 12-31-86

Signed Steve Albrecht
(TECHNICIAN)

MV. NO. 15697
13-36

STATE CORPORATION COMMISSION
DEC 30 1986
CONSERVATION DIVISION
Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 12 15 1986 month day year

API Number 15-101-21,352-0000

OPERATOR: License # 6113 Name Landmark Oil Exploration, Inc. Address 110 S. Main, Suite 510 City/State/Zip Wichita, Kansas 67202 Contact Person Jeffrey R. Wood Phone 316-265-8181

NE NW SE Sec 14 Twp 17 S, Rg 27 X East 2310 1650 Ft. from South Line of Section Ft. from East Line of Section

CONTRACTOR: License # 5422 Name Abercrombie Drilling, Inc. City/State Wichita, Kansas

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 330 feet County Lane

Well Drilled For: X Oil SWD Infield Mud Rotary Gas Inj X Pool Ext Air Rotary OWWO Expl Wildcat Cable

Lease Name Hagans Well # 1-14 Ground surface elevation feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water 200 Depth to bottom of usable water 1250'

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Surface pipe by Alternate: 1 X Surface pipe planned to be set 250' Conductor pipe required Projected Total Depth 4650 feet Formation Mississippi

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 12-12-86 Signature of Operator or Agent Robert C. Patton Title Exploration Manager

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt. This Authorization Expires 6-12-87 Approved By 12-12-86

SPLUD 12-17-86 surface pipe set 265'

Handwritten signature and initials

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Anhydrite 50 feet depth with 50 SXS of 2nd plug @ Cheyenne 80 feet depth with 80 SXS of 3rd plug @ 50' below surface 50 feet depth with 50 SXS of 4th plug @ 40' to surface 10 feet depth with 10 SXS of 5th plug @ feet depth with SXS of

(1) Rathole with 10 (2) Rathole with 10

PUSHER 1/2" 1/2" TD 45-81 FORMATION 11155 SURFACE PIPE 8 5/8 @ 270 ANHYDRITE 2040 ELEVATION 2635 C.C. 2071 STARTING TIME & DATE NOON-12-26-86 COMPLETION TIME & DATE 2:15-PM-12-26-86 1st PLUG @ 2050 FT. W/ 50 SX 2nd PLUG @ 1750 FT. W/ 70 SX 3rd PLUG @ 300 FT. W/ 40 SX 4th PLUG @ 40-0 FT. W/ 10 SX 5th PLUG @ 15 FT. W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 WATER WELL PLUGGED W/ Head - CEMENT COMPANY B.P. Patton TECHNICIAN Dan W.

STATE CORPORATION COMMISSION DEC 30 1986 CONSERVATION DIVISION Wichita, Kansas