

1070115

TO: STATE CORPORATION COMMISSION

API NUMBER 15-101-21,776 -00-00
SW SE SE SEC. 14, T 17 S, R 27 W

CONSERVATION DIVISION - PLUGGING SECTION 340 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MAJOR WELL # 1

TECHNICIAN'S PLUGGING REPORT 1/25/00

COUNTY LANE 149.99

OPERATOR LICENSE # 5046

WELL TOTAL DEPTH 4615 FEET

OPERATOR: RAYMOND OIL COMPANY, INC. PRODUCTION CSG: SIZE " FEET

NAME AND PO BOX 48788 SURFACE CASING: SIZE 8 5/8" @ 285' WITH SX

ADDRESS WICHITA, KS 67201-8788

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SHIELDS DRILLING LICENSE NUMBER 5184

ADDRESS PO BOX 709 RUSSELL, KS 67665-0709

COMPANY TO PLUG AT: HOUR: 8:50 AM DAY: 25 MONTH: 01 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM BURT BEERY

(COMPANY NAME) SHIELDS DRILLING (PHONE) 785-483-3141

WERE:

1ST PLUG AT 2079' WITH 50 SX CEMENT. 2ND PLUG AT 1200' WITH 80 SX CEMENT.

3RD PLUG AT 310' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG 2/3/00

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 11:15 AM DAY: 25 MONTH: 01 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 2079' WITH 50 SX CEMENT. 2ND PLUG AT 1200' WITH 80 SX CEMENT

3RD PLUG AT 310' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL # FLO SEAL BY ALLIED. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED [Signature] (TECHNICIAN) FORM CP-2/3

RECEIVED STATE CORPORATION COMMISSION WICHITA, KANSAS FEB 3 2000

CONSERVATION DIVISION Wichita, Kansas

[Handwritten initials and signature]