

75
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,710-00-00
C NW SE, SEC. 11, T 17 S, R 27 (W/EX)

TECHNICIAN'S PLUGGING REPORT

1980 feet from S section line
1980 feet from E section line

Operator License # 5104
Operator: Blue Goose Drilling Company, Inc.
Name & Address: P.O. Box 1413
Great Bend, KS 67530

Lease Name Hagans Well # 1
County Lane 147.88
Well Total Depth 4550 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 369

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address Great Bend, KS

Company to plug at: Hour: 10:15 a.m. Day: 12 Month: 9 Year: 1986

Plugging proposal received from Mike Gomez
(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4258' PRTD 4219' Perfs at 4195-98, 4190-92, 4056-60'

1st plug sand back to 4000' and dump 3 sx cement on top of sand through bailer,
2nd plug squeeze well with 3 sx hulls, 5 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,
150 sx cement.

Plugging Proposal Received by Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 12 Month: 9 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 4000' and dumped 3 sx cement on top of
sand through bailer,

2nd plug squeezed well with 3 sx hulls, 5 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,
150 sx cement.

Maximum pressure 500 psi and shut in 400 psi.

Remarks: Recovered 1158' 4 1/2" casing. Used 60/40 Pozmix 6% gel by B.J. Titan.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Don Johnson
(TECHNICIAN)

DATE _____
INV. NO. _____

SEP 16 1986