

1 031235

To: 1  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,656 -00-00  
NW NE NE, SEC. 10, T 17 S, R 27 W X

TECHNICIAN'S PLUGGING REPORT

Operator License # 5184

Operator: Shields Oil Producers, Inc.

Name:

Address Shields Bldg.

Russell, KS 67665

330 feet from N X section line

990 feet from E section line

Lease Name Selfridge Well # 1

County Lane

Well Total Depth 3935 127.88 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 219

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Shields Oil Producers, Inc. License Number 5184

Address Shields Bldg., Russell, KS 67665

Company to plug at: Hour: 4 a.m. Day: 4 Month: 7 Year: 19 93

Plugging proposal received from Burt Berry

(company name) Shields Oil Producers (phone) 913-483-3141

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2036-71'

1st plug at 2070' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,

3rd plug at 700' with 25 sx cement, 4th plug at 240' with 40 sx cement,

5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:45 a.m. Day: 4 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 2070' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 700' with 25 sx cement,

4th plug at 240' with 40 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

(If additional description is necessary, use BACK of this report)

I (did not) observe this plugging.

Signed Steve Durrant (TECHNICIAN)

38141

RECEIVED  
STATE CORPORATION COMMISSION  
JUL - 7 1993  
CONSERVATION DIVISION  
Wichita, Kansas

