

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,538-00-00 ^{120 R}

SW NW NE SEC. 10 T. 17 S. R. 27 W. ^{0663 L 2}

4290' feet from S section line

2310' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Selfridge Well # 1

Operator: A.L. Abercrombie

County Lane 148.20

Name & Address 150 N. Main Suite 801

Well Total Depth 4560' feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 309'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center Wichita, KS 67202

Company to plug at: Hour: 3:00 AM Day: 20 Month: 3 Year: 19 90

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: Fill hole with heavy mud and spot cement through drill pipe. 1st plug at 2055' with 50 spw cement. 2nd plug at 1325' with 80 spw cement. 3rd plug at 340' with 40 spw cement. 4th plug at 40' with 10 spw cement. 5th plug circulate in hole with 15 spw cement. 6th plug circulate mouse hole with 10 spw cement. Anhydrite 2021 to 2053.

Plugging Proposal Received by Michael R Wilson
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:30 AM Day: 20 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT

Fill hole with heavy mud and spot cement through drill pipe. 1st plug at 2055' with 50 spw cement. 2nd plug at 1325' with 80 spw cement. 3rd plug at 340' with 40 spw cement. 4th plug at 40' with 10 spw cement. 5th plug to circulate in hole with 15 spw cement. 6th plug to circulate mouse hole with 10 spw cement.

Remarks: Used 60/40 poz mix w/ 6% gel by Allied
(If additional description is necessary, use BACK of this form.)

NO ~~GO~~ ED Observe this plugging.

Signed Michael R Wilson
(TECHNICIAN)

DATE 3-28-90

27235