

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,356-00-00

S/2 S/2 SE, SEC. 10, T 17 S, R 27 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Operator: Slawson, Donald C.
Name & Address 200 Douglas Building
Wichita, KS 67202

330 feet from S section line

1320 feet from E section line

Lease Name Selfridge "00" Well # 1

County Lane 148.53

Well Total Depth 4570 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Company License Number 5657

Address 200 Douglas Building, 104 South Broadway, Wichita, KS 67202

Company to plug at: Hour: 6 p.m. Day: 9 Month: 1 Year: 19 87

Plugging proposal received from Bob Rowe

(company name) Slawson Drilling Company (phone) 316-793-3561

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2090' with 50 sx cement, 2nd plug at 1200' with 60 sx cement,

3rd plug at 260' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement.

 Plugging Proposal Received by Glen Barber
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9 p.m. Day: 9 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2050' with 50 sx cement,

2nd plug at 1300' with 75 sx cement,

3rd plug at 280' with 50 sx cement,

4th plug at 0-40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

1-16-87

15929

FFB 1 0 1987

STATE CORPORATION COMMISSION

JAN 18 1987

CONSERVATION DIVISION
Wichita, Kansas

Signed Glen Barber
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date December 24 1986 month day year 17

API Number 15- 101-21,356-00-00

OPERATOR: License # 5181 Name SLAWSON, DONALD C. Address 200 Douglas Building City/State/Zip Wichita, Kansas 67202 Contact Person Bill Horigan Phone (316) 263-3201

S/2 S/2 SE Sec. 10 Twp. 17 S, Rg. 27 East 330' Ft. from South Line of Section 1320' Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5657 Name Slawson Drilling Co. City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 330' feet County Lane Lease Name Selfridge 100' Well # 1 Ground surface elevation 2615' GR. (Est.) feet MSL Domestic well within 330 feet: yes no Municipal well within one mile: yes no Surface pipe by Alternate: 1 2 X Depth to bottom of fresh water 120' Depth to bottom of usable water 1100' 1225' Surface pipe planned to be set 240' Projected Total Depth 4700' feet Formation Mississippian

Well Drilled For: Oil SWD Infield Gas Inj Pool Ext. OWWO Expt Well Class: Infield Pool Ext. Wildcat Type Equipment: Mud Rotary Air Rotary Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Western Kansas cementing will be done immediately upon setting production casing. Date 12/23/86 Signature of Operator or Agent Robert B. Jenkins Title District Geologist

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. 4 1/2 This Authorization Expires 6-25-87 Approved By 12-23-86

MOVIN 12-31-86 Set 240 ft 8 5/8

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth (e.g., 2090', 1200', 260', 40', 10'), feet depth with, and size of casing (e.g., 60/40 Poz. w/6% Gel).

Vertical log section with handwritten entries: PUSHED 506 Rows, TD 4570 FORMATION MISS, SURFACE PIPE 4" @ 240' ESK, ANHYDRITE ELEVATION 2615, STARTING TIME & DATE 6:20 AM, COMPLETION TIME & DATE 9:00 PM 1-9-87, 1st PLUG @ 2050 FT. W/ 50 SX, 2nd PLUG @ 1300 FT. W/ 75 SX, 3rd PLUG @ 280 FT. W/ 50 SX, 4th PLUG @ 0.40 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ ✓, WATER WELL PLUGGED W/ ✓, CEMENT COMPANY 6 J T I F N, STATE CORPORATION COMMISSION, TECHNICALIAN JAN 15 1987 CONSERVATION DIVISION Wichita, Kansas