

1 070317

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,551-00-00
SE NW NE, SEC. 35, T 16 S, R 29 W/R
4290 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5063
Operator: Energy Exploration, Inc.
Name & Address 1002 S. Broadway
Wichita, KS 67211

Lease Name Gill Well # 2
County Lane 150.80
Well Total Depth 4640 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 209.5

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422
Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 10 p.m. Day: 17 Month: 6 Year: 19 90

Plugging proposal received from Tony Martin

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841
were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2795'
Anhydrite 2186-2223'

1st plug at 2230' with 50 sx cement, 2nd plug at 1250' with 80 sx cement,
3rd plug at 230' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1 a.m. Day: 18 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2230' with 50 sx cement,
2nd plug at 1250' with 80 sx cement,
3rd plug at 230' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6%rgel 1/2# floseal by B.J. Services.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-27-90
INV. NO. 28507

JUN 20 1990
06-20-1990
CONSERVATION DIVISION
Wichita, Kansas

Signed Dan Goodrow
(TECHNICIAN)

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas

FAX

2000

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

EFFECTIVE DATE: 6-6-90
NOTICE OF INTENTION TO DRILL 101-21,551
Must be provided by the C.C. five (5) days prior to commencing well

Expected Spud Date 6 5 90
month day year

SE NW NE Sec 35 Twp 16 S, Rg 29 East West

4290 feet from South line of Section
1650 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

OPERATOR: License # 5063
Name: Energy Exploration, Inc.
Address: 1002 S. Broadway
City/State/Zip: Wichita, Kansas 67211
Contact Person: Brad Lehl
Phone: 316/267-7336

County: Lane
Lease Name: Gill Well #: 2
Field Name: Terwilliger North

CONTRACTOR: License # 5422
Name: Abercrombie Drilling, Inc.

Is this a Prorated Field? yes X no
Target Formation(s): Mississippian
Nearest lease or unit boundary: 330'

Well Drilled For: Well Class: Type Equipment:
X Oil Inj Infield X Mud Rotary
Gas Storage X Pool Ext. Air Rotary
OWO Disposal Wildcat Cable
Seismic; # of Holes

Ground Surface Elevation: N/A feet MS.
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 180'

If OWO: old well information as follows: N/A
Operator:
Well Name:
Comp. Date: Old Total Depth

Depth to bottom of usable water: 1200'
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 200'
Length of Conductor pipe required: N/A

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

Projected Total Depth: 4630'
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
well farm pond other

DWR Permit #: N/A
Will Cores Be Taken? yes X no
If yes, proposed zone: 200' Alt. II Req.

Exp. 12/1/90 AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Tony Martin

SPUD DATE 6-6-90 INIT. DK

LENGTH SURFACE PLANNED 200' 8 1/8"

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8" @ 209.5 CONDUCTOR
ANHYDRITE-T- 2/86 B- 2223 ELEVATION 2795'
FORMATION MISS

06-26-90
RANGE
Wichita

	DV TOOL	ALT II DONE
	SX	Y N
1	Anhydrite Base @ 2230 Ft. W/ 50 SX	
	1/2 Base Anyh. @	Ft. W/ SX
2	1/2, 1/2 Plug @ 1250 Ft. W/ 80 SX	
3	Bottom Surface @ 230 Ft. W/ 40 SX	
4	40' Plug @ 40 Ft. W/ 10 SX	

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
Pumping from another water well
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN DG DATE 6-15-90

TYPE OF CEMENT 60/40 6% 1/4 # Flo Seal

STARTING TIME 7:00 (AM/PM) DATE 6-6-90

COMPLETION TIME 1:00:00 (AM/PM) DATE 6-18-90

CEMENT COMPANY B.T. Fitter Services