

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,413-00-00

NW NW NW, SEC. 35, T 16 S, R 29 W 6X

4950 feet from S section line

4950 feet from E section line

Lease Name Gill "A" Well # 1

TECHNICIAN'S PLUGGING REPORT

Operator License # 9482

County Lane 150.22

Operator: National Petroleum Reserves, Inc.

Name & Address 260 North Rock Road, Suite 215

Well Total Depth 4622 feet

Wichita, KS 67206

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 5 p.m. Day: 20 Month: 10 Year: 19 87

Plugging proposal received from Ken Lowe

(company name) Red Tiger Drilling Company (phone) 316-263-1201

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2250'

1st plug at 2250' with 50 sx cement, 2nd plug at 1350' with 80 sx cement,

3rd plug at 30' below base of surface pipe with 40 sx cement,

4th plug at 40-0' with 10 sx cement.

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by James R. Kapp (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:30 p.m. Day: 20 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2250' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 260' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 29 1987  
10-29-1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED  
I, \_\_\_\_\_, did not observe this plugging.

Signed James R. Kapp (TECHNICIAN)

C. 11-4-87  
18743

