

22

To: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

API NUMBER 15- 101-20,255-00-00
 150' SW NE NE SW, SEC. 35, T 16 S, R 29 W/X

Approx. 2145 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886 Lease Name Eaton "A" Well # 1

Operator: Chief Drilling Co., Inc. County Lane *148.04*
 Name & Address 905 Century Plaza Building Well Total Depth 4555 feet
Wichita, KS 67202 Conductor Pipe: Size _____ feet
 Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
 Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:00 pm Day: 11 Month: April Year: 19 85

Plugging proposal received from Ronnie Hoover
 (company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4553' Perfs at 4468-72'

1st plug sand back to 4420' and dump 4 sx cement on top of sand through bailer
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls
release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Robert B. Tarbutton
 (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:00 pm Day: 11 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4420' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,
10 sx gel, 1 sack hulls released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED
 STATE CORPORATION COMMISSION
04-23-1985
 APR 23 1985

Maximum pressure 300 psi and shut in 100 psi CONSERVATION DIVISION
 Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. Recovered 2800' 4 1/2" casing.
 (If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Paul A. Luther
 (TECHNICIAN)

5-2-85
7911