

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-20,938-00-00

NE SE SW, Sec. 1, T 16 S, R 29 W/R

990 feet from ~~XX~~/S section line

2310 feet from W/~~XX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Eaton "B" Well # 1

Operator: Chief Drilling Co., Inc.  
Name & 905 Century Plaza  
Address Wichita, KS 67202

County Lane

Well Total Depth 4455 feet 144.78

Conductor Pipe: Size        feet       

Surface Casing: Size 8 5/8 feet 276

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D&A X

Other well as hereinafter indicated       

Plugging Contractor Warrior Drilling Co. License Number 5674

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 5:00 am Day: 28 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Harold Dinkle

(company name) Warrior (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2030' with 50 sx cement

2nd plug at 850' with 50 sx cement

3rd plug at 320' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 10 sx cement

Signed J. A. Metz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All        Part        None X

Operations Completed: Hour: 8:00 am Day: 28 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2030' with 50 sx cement, 2nd plug at 850' with

50 sx cement, 3rd plug at 320' with 40 sx cement, 4th & 5th plugs - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate

rathole with 10 sx cement

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun

MAR 07 1984  
03-07-1984  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I ~~did~~/ did not) observe this plugging.

Signed J. A. Metz  
(TECHNICIAN)

DATE 3-8-84  
0578