

To: 1  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-21,468 0000

NW NE NE, SEC. 5, T 16 S, R 29 W/E

4910 feet from S section line

925 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6194

Lease Name Speer Well # 1

Operator: ESP Development, Inc.

County Lane 142.35

Name & Address RR 1, Box 18

Well Total Depth 4380 feet

Paradise, KS 67658

Conductor Pipe: Size          feet

Surface Casing: Size 8 5/8 feet 224

Abandoned Oil Well          Gas Well          Input Well          SHD Well          D&A X

Other well as hereinafter indicated         

Plugging Contractor Western Kansas Drilling License Number 4083

Address Box 126, Hays, KS 67601

Company to plug at: Hour: 2 a.m. Day: 3 Month: 5 Year: 19 88

Plugging proposal received from Frank Taggart

(company name) Western Kansas Drilling (phone) 913-628-2296

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2030-66' Elevation 2641' GL

1st plug at 2066' with 50 sx cement, 2nd plug at 1333' with 80 sx cement,

3rd plug at 240' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All          Part          None X

Operations Completed: Hour: 7:30 a.m. Day: 3 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2066' with 50 sx cement,

2nd plug at 1333' with 80 sx cement,

3rd plug at 240' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE 5-17-88

INV. NO. 20630

Signed Steve Pfeifer  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 10 10 33 AM '88  
CONSERVATION DIVISION  
Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

101-21, 468-00-00  
API Number 15-~~099-07156~~

Expected Spud Date.....04/25/88.....  
month day year

OPERATOR: License #.....6194.....  
Name.....RSP. Development, Inc.....  
Address.....RR. 1. Box. 1A.....  
City/State/Zip.....Paradise, Kansas.....67658.  
Contact Person.....Jawis Rickett.....  
Phone.....(913) 998-4413.....

..... East  
NW NE NE Sec 5..... Twp 16..... S, Rg 29..... XX West  
.....4910..... Ft. from South Line of Section  
.....925..... Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line.....370..... feet  
County.....Gove LANE.....

CONTRACTOR: License #083.....  
Name.....Western Kansas Drilling.....  
City/State.....Hays, Kansas.....67601.....

Lease Name.....SPART..... Well #.....1.....  
Ground surface elevation.....264.1..... feet MSL

Well Drilled For: Well Class: Type Equipment:  
XX Oil Storage Infield XX Mud Rotary  
Gas Inj Pool Ext Air Rotary  
OWWO Expt XX Wildcat Cable

Domestic well within 330 feet: yes XX no  
Municipal well within one mile: yes XX no

Depth to bottom of fresh water.....180.....  
Depth to bottom of usable water.....1200.....

If OWWO: old well info as follows:  
Operator.....  
Well Name.....  
Comp Date..... Old Total Depth.....

Surface pipe by Alternate: 1 XX  
Surface pipe planned to be set.....200.....

Conductor pipe required.....  
Projected Total Depth.....4600..... feet

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 4/20/88..... Signature of Operator or Agent Greg Engstrom..... Title Agent.....

For KCC Use:  
Conductor Pipe Required..... feet; Minimum Surface Pipe Required.....200 feet per Alt. X 2  
This Authorization Expires 10-20-88..... Approved By FC 4/20/88.....

EFFECTIVE DATE: 4-25-88  
Spud 4-26-88

200 of 8 5/8"

NO  
WELL

..... East  
..... Sec 5..... Twp 16..... S, Rg 29..... XX West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep.....anhyd..... or formation with.....100..... feet of.....60/40 Pnz.....  
2nd plug @ ft. deep.....200..... or formation with.....40..... feet of.....60/40 Pnz.....  
3rd plug @ ft. deep.....40-0..... or formation with..... feet of.....60/40 Pnz.....  
4th plug @ ft. deep..... or formation with..... feet of.....  
5th plug @ ft. deep..... or formation with..... feet of.....  
(2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

(Kd plug) rest

PUSHER Frank Tager  
TD 4380 FORMATION MISS.  
SURFACE PIPE 8 5/8" @ 224  
ANHYDRITE 2066 ELEVATION 2641.64  
STARTING TIME & DATE 2AM 5-28-88  
COMPLETION TIME & DATE 7:30AM  
1st PLUG @ 2066 FT. W/ 50 SX  
2nd PLUG @ 1332 FT. W/ 80 SX  
3rd PLUG @ 240 FT. W/ 40 SX  
4th PLUG @ 40 FT. W/ 10 SX  
RAT HOLE CIRCULATED W/ 15 SX  
MOUSE HOLE CIRCULATED W/ 10 SX  
WATER WELL PLUGGED W/ None SX  
CEMENT COMPANY Allied  
TECHNICIAN S.P.  
60/40 w/ 6" gel  
MAY 0 9 1988  
CONSERVATION DIVISION  
WICHITA, KANSAS  
RECEIVED  
STATE CORPORATION COMMISSION