

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
AUG 31 1977
08-31-1977
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 101 - 20,242 00-00 (of this well)

Operator's Full Name Abercrombie Drilling, Inc.
Complete Address 801 Union Center, Wichita, Kansas
Lease Name Strothman Well No. 1
Location NW NE Sec. 2 Twp. 16 Rge. (E) (W) 29
County Lane Total Depth 4440'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 2:45 P Day 30 Month 8 Year 1977

The above well was plugged as follows:

RTD 4440' 8 5/8 csg set 259' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 1000' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE

8-31-77

WICHITA, KS

5758.00