

15-101-20075-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 3 1973
12-03-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name C. G. G. Drilling Company.

Complete Address 1107 Union National Building, Wichita, Kansas.

Lease Name Eaton Well No. 1

Location NW-SE-SW Sec. 12 Twp. 16 Rge. (E) (W) 29

County Lane Total Depth 4490'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 8:30 AM Day 29 Month 11 Year 1973

The above well was plugged as follows:

249'--8 5/8 " Surface casing, cement circulated with 180 Sx.
Top of Dakota section 675'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 110 Cu. Ft. cement
thru DP from 900' to 575'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE: 12/3/73
INV. NO. 8242-W

Signed: A. L. Dicks
Well Plugging Supervisor