

15-101-20043-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

DEC 20 1972
12-20-1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling, Incorporated,
P. O. Box 18409
Complete Address 4328 East Kellogg, Wichita, Kansas. 67218

Lease Name Lane Ranch Well No. A-1

Location NW-NW-NE Sec. 15 Twp. 16 Rge. (E) (W) 29

County Lane Total Depth 4555'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dunne-Gardner Petroleum, Incorporated,
Address 200 West Douglas, Wichita, Kans. License No.

Operation Completed: Hour 1:45 PM Day 17 Month 12 Year 1972

The above well was plugged as follows:

270'--8 5/8" Surface casin , cement circulated with 230 Sx.
Top of Dakota saction 0 800'.

Circulated hole with heavy mud. Pullèd DP to 1020' and displaced 110 Cu. Ft. cement
thru DP from 1020' to 695'. Pulled DP to 280' and displaced 30 Cu. Ft. cement thru
DP from 280' to 205'. Pulled DP, set bridge 0 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Jihels
Well Plugging Supervisor

RECEIVED
DATE 12/22/72
INV. NO. 6744-U