

15-101-20083-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 23 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name O. A. Sutton,

Complete Address 800 Sutton Place, Wichita, Kansas,

Lease Name Hanks Well No. 2

Location NE-SW-1/4 Sec. 7 Twp. 17 Rge. (E) (W) 27

County Lane Total Depth 1,620'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Cobbart-Janos, Incorporated,

Address 830 Sutton Place, Wichita, Kansas License No.       

Operation Completed: Hour 12:00 PM Day 11 Month 1 Year 1973

The above well was plugged as follows:

359'--3 5/8" Surface casing, cement circulated with 235 Sx.  
top of Dakota section 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 110 Cu. Ft. cement  
thru DP from 975' to 650'. Pulled DP to 375' and displaced 30 Cu. Ft. cement thru  
DP from 375' to 300'. Pulled DP, set bridge 40' with 7 sack hullo and 10 Cu. Ft.  
cement to bottom of collar..

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Dehler  
Well Plugging Supervisor

DATE 1/23/74

INV. NO. 8441-W