

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,094-00-00

JAN 4 1985

LEASE NAME Hanks

NOTICE: Fill out completely and return to Cons. Div. office within 30 days.

WELL NUMBER 1

2970' Ft. from S Section Line

2310' Ft. from E Section Line

SEC. 28 TWP. 17S RGE. 27 XXX or(W)

COUNTY Lane

LEASE OPERATOR CKK Exploration Inc.

ADDRESS P.O. Box 7339, Wichita, Kansas 67207-0339

PHONE# (316) 788-5160 OPERATORS LICENSE NO. 4054

Date Well Completed 12-8-84

Character of Well D & A

Plugging Commenced 12-8-84

~~XXXXXXXX D&A, SWDXXXXXXXXXXXXXXX~~

Plugging Completed 12-8-84

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Dist#1, Bob Tarbutton

Which KCC/KDHE Joint Office did you notify? KCC District Office, Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4700' KB

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Shale, Sand		12.5'	393	8 5/8'	381.1'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

D & A, Plugged as follows: Filled hole w/mud, spot 50 sx 60/40 Pozmix, 2% gel, 3% cc, thru open end drill pipe @ 2100', mud to 1250', spot 50 sx thru open end drill pipe, mud to 440', spot 50 sx thru open end drill pipe, mud to 40', 1 sk hulls & 8 5/8 plug for solid bridge, pumped 10 sx to base of cellar, circulated 15 sx in rathole, circulated 10 sx in mousehole.

(If additional description is necessary, use BACK of this form.)

Completed @ 5:15 PM 12-8-84 by "SUN".

Name of Plugging Contractor COUGAR DRILLING CO., INC. License No. 5138

Address 555 N. Woodlawn, Suite 114, Wichita, KS 67208

STATE OF Kansas COUNTY OF Sedgwick, ss.

John S. Crowe

(Employee of Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John S. Crowe

(Address) 555 N. Woodlawn, #114, Wichita, KS

67208

SUBSCRIBED AND SWORN TO before me this 11th day of December, 19 84



Phyllis A. Freeman
Notary Public

My Commission Expires: 6-9-86