

15-101-20085-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Lane \_\_\_\_\_ County, Sec. 28 Twp. 17 Rge. (E) 27 (W)

Location as "NE/CNW/SW" or footage from lines NE NW SE  
Lease Owner Oil Property Management, Inc.  
Lease Name Sanders Well No. 1  
Office Address 300 Insurance Building, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed Jan. 30 19 74  
Application for plugging filed Sept. 26 19 76  
Application for plugging approved \_\_\_\_\_ 19 \_\_\_\_\_  
Plugging commenced Nov. 5 19 76  
Plugging completed Nov. 9 19 76  
Reason for abandonment of well or producing formation depleted



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4648 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			374'	8 5/8"	374'	none
			4102'	5 1/2"	4102'	3042.88

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded back to 4370' and dumped 5 sacks of cement.

Halliburton Services plugged well pumping in 3 sacks of hulls, 8 sacks of gel and 130 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 2 8 1976  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor PIPE PULLERS, INC.  
Address Box 128, Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Evelyn Roth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 19 76

JENNY KASSELMAN  
NOTARY PUBLIC  
BARTON COUNTY, KANSAS  
MY COM. EXP. JULY 16, 1978

Jenny Kaselman  
Notary Public

My commission expires \_\_\_\_\_

15-101-20085-00-00

DRILLERS LOG

COMPANY: Patrick Petroleum Company  
 330 Page Court  
 Wichita, Kansas 67202

Lease Name: Sanders No. 1  
 NE NW SE  
 28-17-27W  
 Lane County, Kansas

Contractor: Slawson Drilling Company, Inc.  
 408 One Twenty Building  
 Wichita, Kansas 67202

Total Depth: 4645'

Commenced 1-15-74

Completed 1-30-74

Casing: 374' @ 379' 8-5/8" casing

Oil String: 4402' of 5½" run (1-29-74)

0 to 385' 12½" Surface Hole  
 385-430 Shale & Shells  
 430-2030' Shale  
 2030-2096 Shale & Shells  
 2096-2132 Anhydrite  
 2132-2412 Shale & Lime  
 2412-2612 Shale & Lime  
 2612-3690' Lime & Shale  
 3690-3845 Lime  
 3845-3970'  
 3970-4055' Lime & Shale  
 4055-4092 Lime  
 4090-4150 Lime & Shale  
 4150-4525' Lime  
 4525' Ft. Scott  
 4525'-4645' Miss

RECORDED  
 STATE OF KANSAS  
 SEP 2 1974  
 COUNTY OF SEDGWICK  
 WICHITA, KANSAS

State of Kansas

County of Sedgwick

I, James C. Remsberg, of the Slawson Drilling Company, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the Jarvis No. 1 well.

*James C. Remsberg*  
 James C. Remsberg

Subscribed and sworn to me on February 5, 1974

*Mary Lou Taylor*  
 Notary Mary Lou Taylor

My Commission expires January 17, 1977

