

15-101-20142-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Lane c SEC. 27 TWP. 17 S RGE. 27 E/W
Location as in quarters or footage from lines:
NE-NW-SW

Locate Well
correctly on above
Section Platt.

Lease Owner Thunderbird Drilling, Inc.
Lease Name Mumma Well No. 2
Office Address P. O. # 97, Ellinwood, Kansas 67526
Character of Well (Completed as Oil, Gas or Dry Hole): oil
Date Well Completed 2-75
Application for plugging filed 10-21-83
Plugging commenced 11-22-83 10:00 A.M.
Plugging completed 11-22-83 12:15 P. M.
Reason for abandonment of well or producing formation
depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Richard Lacey

Producing formation LKC Depth to top 3988 bottom 4308 T.D. 4308

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	310	none
				5 1/2	4303	none

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Allied Cementing mixed 2 sacks hulls, 10 sacks jell, 50 sacks cement,
10 sacks jell, 200 sacks cement. Pumped down 5 1/2 casing, S.I.P. 50 #.
Mixed 20 sacks cement. Pumped down annulus. Shut in 300 #.
Cement was 60/40, 2 % jell, and 3 % CCL.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing & Thunderbird Drilling, Inc. 5131

STATE OF Kansas COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

RECEIVED
STATE CORPORATION COMMISSION

DEC 30 1983

SUBSCRIBED AND SWORN TO before me this
CONSERVATION DIVISION
Wichita, Kansas

(Signature) Myron E. Usher
P. O. # 97, Ellinwood, Kansas 67526
(Address)

day of November, 1983

Notary Public.

My Commission expires:

