

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101,21,651 - 00-00

LEASE NAME Benson-Atwell

WELL NUMBER 1-23

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1874 Ft. from S Section Line

1874 Ft. from E Section Line

SEC. 23 TWP. 17S RGE. 27 (KK) or (W)

COUNTY LANE

LEASE OPERATOR Vess Oil Corporation

ADDRESS 8100 E. 22nd North, Bldg. 300 Wichita, KS. 67226

PHONE# (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 6-12-93

Plugging Commenced 6-12-93

Plugging Completed 6-12-93

The plugging proposal was approved on June 12, 1993 (Date)

by Glen Barlow (KCC District Agent's Name).

Is ACO-1 filled? by oper. If not, is well log attached? yes

Producing Formation Depth to Top Bottom T.D. 4540'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	332	8 5/8"	332	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

50 sx. @ 2000', 80 sx. @ 1050', 40 sx. @ 360', 10 sx. @ 40', 15 sx. in rathole

Total 195 sx. 60/40 Pozmix, 6% Gel, 1/4# floseal Allied Cementing

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6038

Address R.R. 1 Box 183 B Great Bend, KS. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation


STATE OF Kansas COUNTY OF Barton, ss.

L. D. Davis (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. D. Davis

(Address) R.R. 1 Box 183 B Great Bend, KS 67530



AND SWORN TO before me this 16th day of June, 19 93

Bessie M. DeWerff
Notary Public
Bessie M. DeWerff

My Commission Expires: 5-20-97

15-101-21651-00-00

DRILLERS WELL LOG

0 - 160 Shale & Rock
160 - 970 Shale
970 - 1985 Sand & Shale
1985 - 2015 Anhy.
2015 - 3985 Lime & Shale
3985 - 4158 Lime
4158 - 4210 Lime & Shale
4210 - 4540 Lime
4540 RTD

COMMENCED: 6-03-93
COMPLETED: 6-12-93

VESS OIL CORPORATION
Benson-ATwell #1-23
150' SE of NW SE
Sec. 23-17S-27W
Lane County, KS.

ELEVATION: 2583' GR 2588' KB

SURFACE CASING:

8 5/8" set @ 332' W/225 sx. 60/40
pozmix, 2% gel, 3% cc

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON)^{ss}


L. D. DAVIS of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

L D Davis
L. D. Davis

Subscribed and sworn to before me this 16th day of June 1993.

My Commission expires: 5-20-97

Bessie M. DeWerff
Notary Public: Bessie M. DeWerff



RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1993
CONSERVATION DIVISION
Wichita, Kansas