

API NUMBER 15-101-21,022-00-00

LEASE NAME Whipple

WELL NUMBER 34-6

2970 Ft. from S Section Line

3020 Ft. from E Section Line

SEC. 34 TWP. 17S RGE. 27 (E) or (W)

COUNTY Lane

Date Well Completed 9/14/83

Plugging Commenced 9/9/95

Plugging Completed 9/9/95

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Coas. Div.  
 office within 30 days.

LEASE OPERATOR L. B. Industries, Inc.

ADDRESS 12200 E. Briarwood Ave., Suite 250, Englewood CO 80112

PHONE# (303) 790-8340 OPERATORS LICENSE NO. 3680

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 7, 1995 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Dennis Depth to Top 4206 Bottom 4216 T.O. 4660

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Dennis	Oil	4206	4216	8-5/8"	302	None
				4-1/2"	4626	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Pressure test 8-5/8" x 4-1/2" annulus to 500#, did not pump in.  
 Pumped 90.6 bbls 40/60 Pozmix with 6% gel and with 300 lb. Cotton Seed Hulls in first 25 sx cement, plugged from 4216' to surface.

RECEIVED  
 STATE CORPORATION COMMISSION

Name of Plugging Contractor Halliburton Energy Service SEP 20 1995 License No. 5287

Address Box 428, Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. B. Industries, Inc.

STATE OF Colorado COUNTY OF Arapahoe, ss.

Layle L. Robb (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Layle L. Robb  
 12200 E. Briarwood Ave., Suite 250  
 (Address) Englewood, CO 80112-6702

SUBSCRIBED AND SWORN TO before me this 18th day of September, 1995

Peggy Steffin  
 Notary Public  
 Peggy Steffin

My Commission Expires: 8/11/96  
 USE ONLY ONE SIDE OF EACH FORM