

LEASE NAME Spruill

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 32 TWP 17S RGE. 27W ~~48~~ or (W)

COUNTY Lane

Date Well Completed

Plugging Commenced 5-28-91

Plugging Completed 5-31-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Mull Drilling Co., Inc.

ADDRESS P.O. Box 2758 Wichita, Ks. 67201

PHONE# (316) 264-6366 OPERATORS LICENSE NO. 5144

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

is ACO-1 filled? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	404'	none
				5 1/2"	4652'	800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 4145' dumped 5 sacks cement. Shot pipe @2031', 1523', 1281', 800'. Spotted 80 sacks @1250', pulled to 430' spotted 50 sacks pulled up to 40' and topped off with 10 sacks 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mull Drilling Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

RECEIVED
 STATE CORPORATION COMMISSION SUBSCRIBED AND SWORN TO before me this 6 day of June, 19 91

JUN 07 1991

Doreen Herzberg
 Notary Public

My Commission Expires:



15-101-20491-00-01

Metrn-Log

Radiation Guard Log

COMPANY MULL DRILLING COMPANY

RECEIVED
STATE CORPORATION COMMISSION

WELL # #1 SPAVILL

FIELD _____

'APR 05 1991

COUNTY LANE

CONSERVATION DIVISION
STATE OF KANSAS

Location
150 FT. WEST OF NW-SE-NW
Sec. 32 Twp. 17S Rge. 21W

Other Services:

Permanent Datum: GROUND LEVEL Elev. 2708
Log Measured From K.B. 7 Ft. Above Perm. Datum
Drilling Measured From KELLY BUSHT 26

Elev.: K.B. 2715
D.F. _____
G.L. 2708

Date	<u>11-23-80</u>						
Run No.	<u>ONE</u>						
Depth—Driller	<u>4650</u>						
Depth—Logger	<u>4652</u>						
Btm. Log Inter.	<u>4651</u>						
Top Log Inter.	<u>0</u>						
Casing—Driller	<u>8 5/8</u>	<u>396</u>		•		•	•
Casing—Logger							
Bit Size	<u>7 7/8</u>						
Type Fluid in Hole	<u>CHEMICAL</u>						
Dens.	Visc.	<u>9.0 148</u>					
pH	Fluid Loss	<u>10.0</u>	<u>18.0</u> ml		ml		ml
Source of Sample	<u>FLOWLINE</u>						
R ₁ @ Meas. Temp.	<u>1.4</u>	<u>70</u>	°F	•	°F	•	°F
R ₂ @ Meas. Temp.	<u>1.1</u>	<u>70</u>	°F	•	°F	•	°F
R ₃ @ Meas. Temp.	<u>2.2</u>	<u>70</u>	°F	•	°F	•	°F
Source: R ₁	R ₂	<u>CHAATS</u>					
R ₄ @ BHT	<u>.8</u>	<u>122</u>	°F	•	°F	•	°F
Time Since Circ.	<u>2 HOURS</u>						
Max. Rec. Temp.	<u>122</u> °F				°F		°F
Equip.	Location	<u>H-4</u>	<u>•</u>	<u>DAKLEY</u>			
Recorded By	<u>PORTER</u>						
Witnessed By.	<u>JERRY JESPERSON</u>						