



15-101-20059-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 15 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Oden of Red Tiger Drilling Company has this  
date requested permission to plug the following described well:

Mr. Oden guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Incorporated,

Complete Address: Box #18407, Wichita, Kansas.

Lease Name: Douglas Well No. 1

Location: SW-NW-SW Sec. 13 Twp. 17 Rge. (E)(W)27

County: Lane Total Depth 4580' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Oden was instructed to plug the well as follows:

389'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 600'.

Circulate hole with heavy mud. Pull DP to 825' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 400' and displace 30 Cu. Ft. cement thru DP.  
Full DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

*H. L. Nichols*  
Conservation Division Agent