



15-101-20007-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Virgil Shawn of Sage Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Shawn guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling and Petroleum Resources,

Complete Address: Box #18412, Wichita, Kansas.

Lease Name: Hagans Well No. E-1

Location: SE-NW Sec. 11 Twp. 17 Rge. (E)(W) 27

County: Lane Total Depth 4560' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Shawn was instructed to plug the well as follows:

329'--8 5/8" Surface casing, cement circulated with 235 Sx.
Top of Dakota section @ 1075'.

Circulate hole with heavy mud. Pull DP to 1300' and displace 100 Sx.
cement thru DP. Pull DP to 320' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Dehler
Conservation Division Agent