



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS, 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION DEC 3 1973 15-03-1973 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Lowell Moore of C O G Drilling Company has this

date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: C O G Drilling Company,

Complete Address: 1107 Union National Bldg., Wichita, Kansas.

Lease Name: Eaton Well No. 1

Location: NW-SW-SE Sec. 12 Twp. 16 Rge. (E)(W) 29

County: Reno Total Depth 4490' Oil Well

Gas Well Input Well SWD Well D & A K Lost Hole

Mr. Moore was instructed to plug the well as follows:

2 1/2" -- 8 5/8" Surface casing, cement circulated with 180 Sct. Top of Dakota section 675'

Circulate hole with heavy mud. Pull DP to 900' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge 240' with 2" steel hangers and 10 Cu. Ft. cement to bottom of collar.

Very truly yours,

[Signature] Conservation Division Agent