



15-101-20043-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1972
12-20-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Herb Mason of Dunne-Gardner Petr., Inc., has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Incorporated,

Complete Address: 4328 E. Kellogg, Wichita, Kansas.

Lease Name: Eane Ranch Well No. A-1

Location: NW-NW-NE Sec. 15 Twp. 16 Rge. (E)(W) 29

County: Lane Total Depth 4555' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mason was instructed to plug the well as follows:

270'--8 5/8" Surface casing, cement circulated with 230 Sx.
Top of Dakota section 0'800'.

Circulate hole with heavy mud. Pull DP to 1020' and displace 110 Cu. Ft. cement thru DP. Pull DP to 280' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge 0'40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,


Conservation Division Agent