



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

10 May 1982

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

15-101-20665-00-00

Dear Sir:

Mr. Jim Laftus of Lawson Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Donald C. Lawson Production

Complete Address: 200 Douglas Bldg, Broadway & Douglas Wichita, Kans 67202

Lease Name: Lillison Well No. F 1

Location: S/2 NW-SE Sec. 24 Twp. 16 Rge. 29 (E) (M)

County: Lane Total Depth: 46.30'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Laftus was instructed to plug the well as follows:

They cement circulated 319' of 8 5/8" surface casing. The anhydrite was at 2203'. 1st plug at 1800' with 60 bbls of cement. 2nd plug at 350' with 35 bbls of cement. 3rd plug on solid bridge with 10 bbls of cement 40' to 0'. Then circulated 10 bbls of cement in rat hole. The hole was full of heavy mud while plugging. Halliburton Co. accomplished the plugging.

Very truly yours,

Paul A. Luther  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
05-18-1982  
MAY 18 1982

CONSERVATION DIVISION  
Wichita