

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-20,978-0006

LEASE NAME First Baptist Church

WELL NUMBER 1

4290 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 2 TWP. 17S RGE. 30 (X) or (W)

COUNTY LANE

Date Well Completed 5-25-86

Plugging Commenced 5-29-86

Plugging Completed 5-29-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR L. D. Drilling, Inc.

ADDRESS R.R. 1 Box 183 B Great Bend, Kansas 67530

PHONE# (316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #1 Plugger: Richard Lacey

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Basis Penn Cherokee Depth to Top 4466 Bottom T.D. 4635

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface		0	334'	8 5/8"	334'	none
Production		0	4632	5 1/2"	4632'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

3 sx. Halls, 2 sacks in cement

175 sx. Howco lite--Pressured to 2500# closed in Pumped down the 5 1/2" csg.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No.

Address Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.

L. D. Davis (Employer, Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, help me God.

STATE CORPORATION COMMISSION

(Signature) L. D. Davis

(Address) R.R. 1 Box 183 B

Great Bend, Ks. 67530



SUBSCRIBED AND SWORN TO before me this 30th day of May, 19 86

Wichita, Kansas

Bessie M. DeWerff
Notary Public

My Commission Expires: 5-20-86

Bessie M. DeWerff



15-101-20978-00-00

DRILLER'S WELL LOG

DATE COMMENCED: May 3, 1984
DATE COMPLETED: May 15, 1984

L. D. Drilling
FIRST BAPTIST CHURCH #1
SE NE NE
Sec. 2, T17S, R30 W
Lane County, Ks.

ELEVATION: 2850 K.B.

0 - 229' Surface Soil, Shale, Sand
2229 - 2256' Anhydrite
2856 - 3902' Shale & Lime
3902 - 3906' Shale
3906 - 3921' Lime & Shale
3921 - 4202' Lime
4202 - 4312' Shale
4312 - 4402' Lime, Shale, Chert
4402 - 4525' Lime
4525 - 4635' Chert & Lime
4635' RTD

FORMATION DATA

Anhydrite	2229'
Hachmer	3902'
Toronto	3921'
Lansing	3943'
Stark	4202'
Hushpuckney	4238'
Marmaton	4312'
Pawnee	4402'
Mississippi	4525'
RTD	4635'

Surface Pipe: Set new 8-5/8"
23# pipe @334' w/200 sacks
50/50 pozmix 2% gel 3% cc.

Production Pipe: Set new 5 1/2"
14# @4632 1/2' w/50 sacks 50/50
pozmix 2% gel 18% salt & 3/4 of
1% CFR2 and 100 sacks 50/50
pozmix 2% gel 18% salt & 3/4
of 1% CFR2 5# Gilsonite w/20
Bbls. salt flush ahead.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and statements
herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 21 day of May 1984.

My Comm. Expires:

4-29-86

Dorothy M Hague
Notary Public

RECEIVED
STATE CONSERVATION COMMISSION
MAY 16 1984
CONSERVATION DIVISION
Wichita Falls