

15-135-3092-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ness County, Sec. 19 Twp. 17S Rge. 22W (E) (W)

Location as "NE/CNW/SW" or footage from lines. C SW SE

Lease Owner Slawson Drilling Co., Inc.

Lease Name Everhart Well No. B-#1

Office Address 408 One-Twenty Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2-9-66 19

Application for plugging filed 2-9-66 19

Application for plugging approved 2-9-66 19

Plugging commenced 2-9-66 19

Plugging completed 2-9-66 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker, Victoria, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4460 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	255'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed Plug to 540', put in 20 sks. cement through drill pipe  
Pushed Plug to 245', put in 20 sks. cement  
Filled hole w/mud to 40', set plug w/1/2 sk. hulls and 10 sks. cement

RECEIVED  
STATE CORPORATION COMMISSION

FEB 15 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 14th day of February, 1966

My commission expires April 1, 1967

Ulanda Nichols  
Notary Public.

DRILLER'S LOG

COMPANY: Slawson Drilling Co., Inc.  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: EVERHART B-#1  
 LOCATION: C SW SE Sec. 19-17S-22W  
 NESS COUNTY, KANSAS  
 COMMENCED: 1-30-66  
 COMPLETED: 2-9-66

-----

0	255	Shale
255	1572	Shale, Redbed
1572	1610	Anhydrite
1610	1625	Shale
1625	2305	Shale, Shells
2305	2490	Lime, Shale
2490	2760	Lime
2760	3675	Lime, Shale
3675	4149	Lime
4149	4310	Lime, Shale
4310	4335	Lime
4335	4432	Chert
4432	4460	Lime
	<u>4460</u>	<u>RTD - D. &amp; A.</u>

RECEIVED  
 STATE OF KANSAS  
 FEB 15 1966  
 NOTARY PUBLIC  
 WICHITA, KANSAS

-----

Set 8 5/8" used surface casing @ 255' with 175 sacks HA5 Posmix 60-40

-----

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Everhart B-#1 well, located C SW SE of Section 19, Township 17 South, Range 22 West, Ness County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 14th day of February, 1966.

Ulanda Nichols  
 Ulanda Nichols

My Commission Expires:  
 April 1, 1967