

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-22,723-0000

LEASE NAME Squier "A"

WELL NUMBER 1

SPOT LOCATION C W/2 SW SW

SEC. 21 TWP. 17S RGE. 22 ~~K&W~~ (W)

COUNTY Ness

Date Well Completed 12/7/84

Plugging Commenced 12/7/84

Plugging Completed 12/7/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Production Company

ADDRESS Box 351, Liberal, Kansas 67901

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 5469

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City - Richard Lacey

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 4350

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	824	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 50 sxs cement at 1560, 40 sxs at 870, 40 sxs at 420, 10 sxs 40-0, 15 sxs rathole, 60-40 Pozmix, 2% Gel, 3% CaCl.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____
Address Ness City, Kansas

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Seward, ss. JAN 02 1985

Paul Campbell (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Paul Campbell
Paul Campbell, Division Operations Manager
(Address) Box 351, Liberal, Kansas 67901

SUBSCRIBED AND SWORN TO before me this 07 day of December, 19 84

ELIZABETH J. HOOPER
Seward County, Kansas
My Appt. Expires 7-26-87

Elizabeth J. Hooper
Notary Public

My Commission expires:

DRILLERS LOG

OPERATOR: Anadarko Production Company
 Box 351
 Liberal, KS 67901

LEASE NAME: #1 Squier 'A'
 W/2 SW SW Sec 21-17-22W
 Ness County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
 200 Douglas Bldg.
 Wichita, KS 67202

RTD: 4350'

SURFACE CASING: 8 5/8" set at 824' with 475 sx cement

0' to 828' 12 1/4" Surface Hole
 828' to 1525' Sand & Shale
 1525' to 1542' Shale
 1542' to 1585' Stone Corral
 1585' to 2500' Shale
 2500' to 3235' Shale & Lime
 3235' to 4297' Lime & Shale
 4297' to 4315' Shale & Dolomite
 4315' to 4350' Chert, Lime
 4350' RTD

STATE OF KANSAS


COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state the above is an accurate copy of the drillers log for the #1 Squier 'A' for Anadarko Production Company.

James C. Remsberg
 James C. Remsberg, President

Subscribed and sworn to me this 17th day of December, 1984

Rebecca Wold
 Rebecca Wold, Notary



RECEIVED STATE CORPORATION COMMISSION

JAN 02 1985

CONSERVATION DIVISION
Wichita, Kansas

