


15-135-00360-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 27 Twp. 17 Rge. 22 (W)

Location as "NE/CNW/SW" or footage from lines C SE NE

Lease Owner Skelly Oil Company

Lease Name Inez Keatley Well No. 1

Office Address Box 649, McCook, Nebraska

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-9-64 19

Application for plugging filed 6-9-64 19

Application for plugging approved 6-9-64 19

Plugging commenced 6-9-64 19

Plugging completed 6-9-64 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4417 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	318'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug 1/3 sk. hulls @ 600' 20 sks. cement
Plug 1/3 sk. hulls @ 240' 20 sks. cement
Plug 1/3 sk. hulls @ 40' 10 sks. cement
Plugged by Halliburton

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Leslie Kite

P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of June, 1964.

My commission expires April 1, 1967

Ulanda Nichols
Notary Public.

DRILLER'S LOG

COMPANY:
 CONTRACTOR:
 FARM:
 LOCATION:
 COMMENCED:
 COMPLETED:

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 16 1964
 CONSERVATION DIVISION
 Wichita, Kansas

Skelly Oil Company
 LEBEN DRILLING, INC.
 INEZ KEATLEY #1
 C SE NE Sec. 27-17-22
 NESS COUNTY, KANSAS
 5-28-64
 6-9-64

0	50	Surface Clay & Shale
50	240	Shale & Shells
240	320	Sandy Shale & Shale
320	360	Shale
360	550	Shale & Shells
550	625	Sandy Shale
625	985	Shale & Shells
985	1160	Sand
1160	1340	Red Rock & Sand
1340	1570	Shale & Redbed
1570	1605	Anhydrite
1605	1630	Shale
1630	1640	Pyrite
1640	1935	Shale
1935	2225	Shale & Broken Lime
2225	2545	Lime
2545	2680	Lime & Shale
2680	3140	Lime
3140	3453	Shale & Lime
3453	3706	Lime & Shale
3706	3917	Lime
3917	3987	Lime & Chalk
3987	4312	Lime
4312	4393	Lime & Chert
4393	4417	Lime
	4417	<u>Rotary Total Depth - D. & A.</u>

Set 8 5/8" used surface casing @ 318' with 290 sacks Common HA5

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Inez Keatley #1 well, located C SE NE of Section 27, Township 17, Range 22, Ness County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me a Notary Public, in and for Barton County, Kansas, this 15th day of June, 1964.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires
 April 1, 1967