


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 16 Twp 17S Rge 22 (XX) (W)

Location as "NE/CNW/SW" or footage from lines. C SE SE

Lease Owner Ferguson Oil Company

Lease Name Weeks Well No. 1

Office Address 522 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 9/27/62 19

Application for plugging filed 9/27/62 19

Application for plugging approved 9/27/62 19

Plugging commenced 9/27/62 19

Plugging completed 9/27/62 19

Reason for abandonment of well or producing formation no oil or gas found in commercial quantities

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 4418 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	252'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Started plugging 12:00 noon, set plug 600' and cement through drill pipe with 20 sacks cement. Fill hole with rotary mud to 240', set plug and cement with 20 sacks through drill pipe. Fill hole with mud to 40' of base of cellar and cap with 10 sacks cement, plugging completed 2:00 PM

RECEIVED
STATE CORPORATION COMMISSION
10-4-62
OCT 4 1962

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.

Address 412 Union Center, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss. Wilson Rains - Partner of Rains & Williamson Oil Co.

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
412 Union Center
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of October, 1962

My commission expires January 25, 1965

Janet Johnson
Notary Public.

ROTARY DRILLING LOG

No. 1 Wells
 C SE SE Section 16-17S-22W
 Ness County, Kansas

Operator: Ferguson Oil Company
 Contractor: Rains & Williamson Oil Co.
 Commenced: 9/15/62
 Completed: 9/27/62

Remarks: Elevation 2311 DF
 set 252' of @ 5/8" with
 140 sacks sunset cement

FORMATIONS:

Surface Soil - Clay	40'
Shale	250'
Shale & Sand	1110'
Shale & Shells	1750'
Shale & Lime	2300'
Lime & Shale	2680'
Lime	3145'
Lime & Shale	3325'
Lime	3750'
Lime & Shale	3945'
Lime	4418'
Rotary/Depth (D&A)	4418'

RECEIVED
 STATE CORPORATION COMMISSION

OCT 1 1962

CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

BY: *Wilson Rains*
 Wilson Rains - Partner

Subscribed and sworn to before me a Notary Public in and for the State of Kansas, County of Sedgwick, this 1st day of October, 1962.

My Commission Expires:
 January 29, 1965

Janet Johnson
 Janet Johnson