


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ness County, Sec. 14 Twp. 17S Rge. 22 NW  
Location as "NE/CNW, SW" or footage from lines  
C NW SW

Lease Owner Liberty Enterprises, Inc.  
Lease Name Majors Well No. 1  
Office Address 305 West Mill, Plainville, KS 67663  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed 6/27/77 19  
Application for plugging filed 6/27/77 19  
Application for plugging approved 6/27/77 19  
Plugging commenced 6/27/77 19  
Plugging completed 6/27/77 19  
Reason for abandonment of well or producing formation

Too low structurally  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, KS  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4329'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	266.62'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Filled with heavy mud to 660'. Set  
plug. Put in 70 sacks cement. Filled with heavy mud to 240'. Set plug. Put in 20  
sacks cement. Filled with heavy mud to 40'.  
Set plug. Filled to top with 1 sack hulls and 10 sacks cement 50-50 poz 6% gel.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 06 1977  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G DRILLING CO.  
1107 DOUGALS BLDG, 104 SOUTH BROADWAY, WICHITA, KS 67202

STATE OF KANSAS COUNTY OF SEDGWICK ss:  
G F GALLOWAY (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.


(Signature) *G F Galloway*  
G. F. GALLOWAY

1107 DOUGLAS BLDG, Wichita, KS 67202

Subscribed and sworn to before me this 5th day of July, 1977

My commission expires March 3, 1980

*Debra L Heersche*  
Debra L Heersche Notary Public



W E L L L O G

OPERATOR: LIBERTY ENTERPRISES INC  
 WELL NAME: MAJORS #1 LOCATION: C NW SW  
 COUNTY: NESS STATE: KANSAS  
 WELL COMMENCED: 6/18/77 WELL COMPLETED: 6/27/77  
 ELEVATION: 2283' KB TOTAL DEPTH: 4329'  
 PRODUCTION: D & A RIG NO: 1  
 CASING - 8-5/8": 7 JTS, 266.62' W/145 SXS COMMON +2% Gel +3% CC.  
 5-1/2": \_\_\_\_\_

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	995	SHALE & SAND		
995	1225	SAND		
1225	1570	SHALE & RED BED		
1570	1604	ANHYDRITE		
1604	2020	SHALE-LIME		
2020	2300	SHALE & SHELLS		
2300	2635	SHALE-LIME		
2635	3810	LIME & SHALE		
3810	4329	LIME & RTD		

RECEIVED  
 STATE COMMISSIONER OF  
 JUL 06 1977  
 CONSERVATION AND GROUND WATER  
 WICHITA, KANSAS

DST #1: 4274-4312' 30-30-30-30. Weak blow thruout test. Rec 80' Mud W/spots oil. IBHP 1181#, FBHP 1115#, IFP 56#, FFP 73#.

DST #2: 4312-4324' 30-30-30-30. Good blow thruout test. Rec 810' water. IBHP 1278#, FBHP 1262#, IFP 156#, FFP 341#.

STATE OF KANSAS )  
 COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway  
 G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, This 5TH day of JULY, 1977.

MY COMM. EXP. March 3, 1980

Debra L Heersche  
 Debra L Heersche NOTARY PUBLIC

