

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

108P

API NUMBER 15-135-22,946-0000

LEASE NAME Pfaff

WELL NUMBER #A-1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4290 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR NuOil Company, Inc.

SEC. 12 TWP. 17 RGE. 22 (E) or (W)

ADDRESS 1407 Vine, Hays, KS 67601

COUNTY Ness

PHONE# (913) 625-3550 OPERATORS LICENSE NO. 4523

Date Well Completed 11-1-85

Character of Well D & A

Plugging Commenced 11-1-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-1-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.  
to be filed

Is ACO-1 filed? by operator if not, is well log attached? Yes

Producing Formation None Depth to Top \_\_\_\_\_ Bottom T.D. 4455'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From GL.	To	Size	Put in	Pulled out
			208	8 5/8"	208'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug @ 1682' w/40 sks. thru drill pipe; Next plug @ 700' w/70 sks. Cement thru dr pipe; Next Plug @ 240' w/40 sks. Cement thru drill pipe; Top Plug @ 40' w/10 sks. Cement & 4 sk. Hulls thru drill pipe; 10 sks. Cement in Rathole. Well was Cemented w/170 sks. 60/40 Poz, 6% Gel, 3% CC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Williamson Drilling, Inc. License No. 4087

Address 5501 Navajo, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Terry L. Williamson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Terry L. Williamson

(Address) 5501 Navajo, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 5th day of November, 19 85.

My Commission Expires: STATE CORP. COMMISSION

Kim Williamson  
Notary Public

JAN 27 1986

