

15-135-30303-00-00

Form CP-4


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NESS County, Sec. 13 Twp 17 Rge 22W (E) (W)  
Location as "NE/CNW/SW" or footage from lines 100' W OF C SE NW  
Lease Owner RUDY HERMAN  
Lease Name KLEVANS Well No. 1  
Office Address P.O. BOX 348, RUSSELL, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed 19  
Application for plugging filed FEBRUARY 15 19 67  
Application for plugging approved 19  
Plugging commenced FEBRUARY 16 19 67  
Plugging completed FEBRUARY 26 19 67  
Reason for abandonment of well or producing formation NOT COMMERCIAL

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well LEO MASSEY  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4295 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	308	MBNE
				5 1/2"	4288	1999

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

4295	-	4275	-	SAND
4275	-	4235	-	5 SACKS CEMENT
4235	-	560	-	12 SACKS MUD, 30 SACKS CEMENT
560	-	290	-	25 SACKS CEMENT
290	-	55	-	MUD
55	-	45	-	ROCK BRIDGE
45	-	BASE	-	15 SACKS CEMENT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 24 1967

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF BARTON, ss.  
T.L. NUTT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

BOX 562, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 13TH day of MARCH, 19 67

Mary M. Guernsey

Notary Public.

My commission expires JULY 31, 1970

DRILLER'S LOG

Well Owner: Mary A. Herman  
 Farm Name: Kleweno 100' W of Center, SE NE  
 Date Started: 12-26-66 Section 13-17S-22W  
 Date Completed: 1-9-67 Ness County, Kansas  
 Total Depth: 4295

Casing: 8-5/8" set at 306' cemented  
 5 1/2" set at 4288' cemented


Contractor: Peel Brothers, Inc.

Figures below are the bottoms of formations -

Clay, Sand, Shale	0 - 311
Shale	975
Shale and Sand	1242
Red Bed	1555
Anhydrite	1589
Shale and Shells	1935
Shale and Lime	2325
Lime and Shale	3783
Lime	4295
Total Depth	4295

This is to certify that the above information is to the best of our knowledge true and correct.

PEEL BROTHERS, INC.



Wendell C. Peel  
 President

SUBSCRIBED AND SWORN to before me this 10th day of January, 1967.

*Ethel S. Williams*  
 RECEIVED  
 Ethel S. Williams CORPORATION COMMISSION  
 Notary Public

MAR 31 1967

My Commission expires 6-21-70

CONSERVATION DIVISION  
 Wichita, Kansas