

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-135-22,673-00-00

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME Alberta

WELL NUMBER 1

SPOT LOCATION NW-SE-NW

SEC. 13 TWP. 17 RGE. 22 (E) OR (W) (W)

COUNTY Ness

DATE WELL COMPLETED 10-15-84

PLUGGING COMMENCED 5-16-85

PLUGGING COMPLETED 5-16-85

LEASE OPERATOR Nesco Inc

ADDRESS Box 177 Bazine, Ks 67516

PHONE # (913) 398-2573 OPERATORS LICENSE NO. 9692

CHARACTER OF WELL D&A
OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City, Kansas

IS ACC-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? Yes

PRODUCING FORMATION Miss DEPTH TO TOP 4280 BOTTOM 4290 T.D. 4290

HOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Surface pipe	0	314	8 5/8	314	None
	Production	0	4287	4 1/2	4287	1550

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Plug at 4000 with 2 sacks cement. Packer plug at 4130, sand plug at 4230 to 4290 in 4 1/2 pipe. Started at 10:00 AM May 16, 1985 with 3 sacks hull, 15 sacks Jell, 50 sacks cement. 60-40 2% jell 3% cc 10 sacks jell 1 hull 8 5/8 Plug. 125 sacks cements 60-40-2% jell 3% cc 500 lbs. pumping pressure at 1000 lbs. max & 250 lbs shut in pressure and completed job at 11:55 AM May 16, 1985

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Allied Cementing LICENSE No. _____
ADDRESS Ness City Kansas

STATE OF Kansas COUNTY OF Ness SS.

Edward P Leiker (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Edward P Leiker
(ADDRESS) HC 32 Box 132 Hays Ks.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 5 DAY OF June, 1985

Susan M. Leiker
NOTARY PUBLIC



MY COMMISSION EXPIRES: _____

RECEIVED

STATE CORPORATION COMMISSION

JUN 05 1985

FORM CP-4
REVISED 06-83

CONSERVATION DIVISION
Wichita, Kansas