

15-135-20746-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ness SEC. 13 TWP. 17S RGE. 22W E/W
Location as in quarters or footage from lines:

Locate Well
correctly on above
Section Platt.

C of SW-NW
Lease Owner Industrial Supply, Inc.
Lease Name Kleweno Well No. 1
Office Address R.R. 2 Box 118 Winfield, Mo. 63389
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed
Application for plugging filed
Plugging commenced 8-11-81
Plugging completed 8-17-81
Reason for abandonment of well or producing formation

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation _____ Depth to top _____ bottom _____ T.D. 4361

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	293'	none
				5-1/2"	4359'	2524'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Moved in on location, ran sand to 4300' and 5 sacks cement. Shot pipe @3512',
3277', 3112', 3007', 2906', 2804', 2712', 2604' and 2520'. Pulled 62 joints.
Plugged well with 23 sacks gel, 5 sacks hulls, 140 sacks 50/50 pos, 12% gel, 3% cc.
Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
R. Darrell Kelso
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of August, 19 81

My Commission expires:



RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1981

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

COMPANY: John Eaton, Shields, Kansas 67854
 CONTRACTOR: Hellar Drilling Company, Inc., 339 Union Center Bldg., Wichita, Kansas 67202
 LEASE: #1 Kleweno
 LOCATION: c SW NW 13-17S-22W, Ness County, Kansas
 COMMENCED: April 28, 1973
 COMPLETED: May 9, 1973
 CASING: Set 8 5/8" Surface Casing @ 293' w/175 sacks cement

0-293	Surface soil & clay
293-985	Shale & Red Bed
985-1285	Shale & Red Bed & Sand
1285-1582	Shale
1582-1619	Anhydrite
1619-1790	Shale
1790-2265	Shale & Red Bed
2265-2440	Lime
2440-2515	Lime & Shale (Ft. Riley) & Chert
2515-3625	Lime & Shale
3625-3740	Lime & Shale (Topeka)
3740-3844	Lime & Shale
3844-3952	Lime
3952-4054	Lime (L.K.C.)
4054-4320	Lime
4320-4325	Miss.
4325-4330	Lime
4330-4361	Miss.
4361	Rotary Total Depth

D & A

RECEIVED
 STATE CORPORATION COMMISSION
 .1111 - 6 1981
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Kleweno, located in c SW NW 13-17S-22W, Ness County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 10th day of May, 1973.

Catherine Darcey
 Notary Public - Catherine Darcey

My Commission Expires:
 March 25, 1976.